


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

PAWNEE County. Sec. 8 Twp. 20S Rge. 17W (E) (W)
Location as "NE/CNW/SW" or footage from lines SW SW SE
Lease Owner BARBARA OTL COMPANY
Lease Name GONARD Well No. 1
Office Address 322 Central Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 9-14-57 19
Application for plugging filed 9-14-57 19
Application for plugging approved 9-14-57 19
Plugging commenced 9-14-57 19
Plugging completed 9-14-57 19
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well _____
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3980 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	360	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud to 420' cemented with 50 sacks cement. Filled to 359' with heavy mud & cemented with 30 sacks cement. Filled with heavy mud to 20' of ground level then set with 5 sacks on top of solid bridge.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor K & E DRILLING, INC.
Address 719 Union Center, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Dale Silcott (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dale Silcott
Dale Silcott of K & E DRILLING, INC.
719 Union Center, Wichita 2, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 20th day of September 1957
Patricia M. Edwards, Notary Public.

My commission expires 11 August 1958.

PLUGGING
FILE SEC. 8 T. 20 R. 17W
BOOK PAGE 45 LINE 31

SEP 21 1957
STATE CORPORATION COMMISSION
CONSERVATION DIVISION

W E L L LOG

OPERATOR:	BARBARA OIL COMPANY 322 Central Building Wichita 2, Kansas	FARM NAME:	#1 CONARD
CONTRACTOR:	K & E DRILLING, INC. 719 Union Center Building Wichita, Kansas	LOCATION:	SW SW SE, 8-20S-17W Pawnee County Kansas
CASING:	8-5/8" @ 360' (200 sx)	COMMENCED:	9-5-57
R.T.D.	3980 RTD	COMPLETED:	9-14-57
		PRODUCTION:	D & A

FORMATION RECORD

Depths shown indicate bottom of formations encountered.

Surface soil & Clay	45
Shale	155
Sand	175
Shale & Shells	360
Shale, Shells & Sand	550
Red Bed & Shale	755
Shale & Shells	1850
Salt & Shale	1980
Shale & Shells	2150
Shale & Lime	2310
Lime	2450
Shale & Lime	3415
Lime & Shale	3540
Lime	3935
Conglomerate Chert & Shale	3944
Arbuckle Lime	3960
Lime	3980
R.T.D.	3980

CERTIFICATION

STATE OF KANSAS)
) SS:
COUNTY OF SEDGWICK)

I, Dale Silcott of K & E DRILLING, INC., upon oath state that the above and foregoing is a true and correct copy of the log of the BARBARA OIL COMPANY #1 CONARD well.

Dale Silcott

Dale Silcott

Subscribed and sworn to before me this 20th day of September 1957.

Patricia M. Edwards

Patricia M. Edwards, Notary Public

My commission expires: 11 August 1958.

RECEIVED
COMMISSION
SEP 21 1957
COUNTY OF SEDGWICK
WICHITA, KANSAS

PLUGGING
FILE SEC: 8-T-20 R 17W
BOOK: PAGE 45 LINE 31