


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Pawnee County. Sec. 19 Twp. 20 Rge. 18 (E) 18 (W)
Location as "NE/CNW/SW" or footage from lines NE NE SE
Lease Owner Musgrove Petroleum Building, Wichita, Kansas.
Lease Name FOX Well No. 1
Office Address 518 Petroleum Building, Wichita, Kansas.
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed September 9, 1954
Application for plugging filed verbally - September 9, 1954
Application for plugging approved verbally - September 9, 1954
Plugging commenced September 9, 1954
Plugging completed September 9, 1954
Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? verbally - yes.

Name of Conservation Agent who supervised plugging of this well _____
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4215 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	336'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with mud to 325'.
Set first plug at 325' with 25 sx. cement.
Filled hole with mud to 35'.
Set second plug at 35' with 10 sx cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Musgrove Petroleum Corporation,
Address 518 Petroleum Building, Wichita, Kansas.

STATE OF KANSAS, COUNTY OF Sedgwick, ss.
L. Gordon L. Koelling (employee of owner) or (owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) L. Gordon L. Koelling
518 Petroleum Building, Wichita, Kansas.
(Address)

SUBSCRIBED AND SWORN TO before me this 14th day of September 1954
Thomas L. Stinson
Notary Public.

My commission expires September 24, 1956.

PLUGGING
FILE SEC 19 TWP 20 R 18
BOOK PAGE 63 LINE 13

INDEXED
WICHITA, KANSAS

CONTRACTOR'S WELL LOG

COMPANY: Musgrove Petroleum Corporation
 CONTRACTOR: Musgrove Petroleum Corporation
 FARM: FOX #1
 LOCATION: NE NE SE, Sec. 19-20-18
 Pawnee County, Kansas.
 COMMENCED: August 23, 1954
 COMPLETED: September 9, 1954

0	336	Sand & blue shale
336	885	Shale & shells
885	1304	Red bed & shale
1304	1330	Anhydrite
1330	1470	Red bed, shale & sand
1470	2065	Shale & red bed
2065	3400	Lime & shale
3400	3470	Lime
3470	3675	Lime & shale
3675	3722	Lime & shale
3722	3855	Lime
3855	3900	Lime & shale
3900	4025	Lime
4025	4057	Lime & shale
4057	4110	Lime
4110	4137	Lime & chert
4137	4159	Lime & shale
4159	4215	Arbuckle & lime
	4215	Rotary Total Depth

Set 8-5/8" surface at 336' with 175 sacks cement & 1 calcium chloride
 Dry and Abandoned.

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

I, GORDON L. KOELLING, do hereby certify that the above and foregoing is a true and correct copy of the log of the FOX #1, NE NE SE, Section 19-20-18, Pawnee County, Kansas, as reflected by the files of the Musgrove Petroleum Corporation.

MUSGROVE PETROLEUM CORPORATION

BY *Gordon L. Koelling*
 Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 14th day of September, 1954.

William S. Starnamp
 Notary Public

My commission expires September 24, 1954.

PLUGGING
 FILE SEC 19-20 R 116
 BOOK PAGE 63 LINE 43