


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

NORTH



Locate well correctly on above Section Plat

Pawnee County, Sec. 11 Twp 20S Rge. 18W (X) (W)
Location as "NE/CNW/SW" or footage from lines SW NW SW
Lease Owner Imperial Drilling Company, Inc.
Lease Name Black Well No. 1
Office Address 903 Union National Bank Bldg., Wichita, Ks.
Character of Well (completed as Oil, Gas or Dry Hole) dry hole
Date well completed April 23, 19 54
Application for plugging filed April 23, 19 54
Application for plugging approved April 23, 19 54
Plugging commenced April 23, 19 54
Plugging completed April 23, 19 54
Reason for abandonment of well or producing formation
No commercial shows of oil.

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well M. A. Rives, Box, 8, Pratt, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4064 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	346'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set #1 plug at 300' with 35 sacks cement. Filled hole with rotary mud to 35'. Set #2 plug with 15 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
MAY 4 - 1954
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Imperial Drilling Company, Inc.
Address 903 Union National Bank Building, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Raymond L. Bacon (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) By: Raymond L. Bacon Vice-
903 Union Natl Bank Bldg. Pres.
Wichita 2, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 30th day of April, 19 54

Notary Public.

My commission expires November 9, 1957

PLUGGING
FILE SEC 11 T 20 R 18 W
BOOK PAGE 27 LINE 39

DRILLER'S LOG

Imperial Drilling Company, Inc.
903 Union National Bank Building
Wichita 2, Kansas

Black #1
SW NW SW Sec. 11-20S-18W
Pawnee County, Kansas

Total Depth: 4064'

Commenced: 4-10-54 Completed: 4-23-54 Elevation: 2157' K.B.
Production: D & A

Contractor: Imperial Drilling Company, Inc.,
Wichita, Kansas

Casing Record: Set 346' of 8-5/8" Surface Pipe W/175 Sacks Cement.

Figures indicate bottom of formations:

			<u>TOPS</u>
Surface Clay, Sand & Shale	150'		
Shale and Shells	635'	Anhydrite	1230' (/927)
Dakota Sand	825'	Heebner	3539' (-1382)
Red Bed and Shale	1230'	Lansing	3591' (-1434)
Anhydrite	1255'	Conglomerate	4004' (-1847)
Shale and Shells	2035'	Arbuckle	4024' (-1867)
Lime and Shale	2405'	Rotary Total Depth	4064' (-1907)
Lime - "hard"	2460'		
Lime and Shale	3405'		
Lime	4064'		
Total Depth	4064'		

RECEIVED
STATE CORPORATION COMMISSION
MAY 4 - 1954
CORPORATION DIVISION
Wichita, Kansas

We hereby certify this to be a correct and accurate log of the above described well as shown on the daily drilling reports.

IMPERIAL DRILLING COMPANY, INC.

By: Raymond L. Bacon
Vice-President

Subscribed and sworn to before me this 25th day of April, 1954.

Marilyn E. Fox
Notary Public

My Commission Expires: November 9, 1957.

