


STATE OF KANSAS
STATE CORPORATION COMMISSION.

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Kiowa County, Sec. 24 Twp. 28 Rge. 19 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines _____
C NE NW
Lease Owner Oil Properties Co., Inc.
Lease Name Seacat #1 Well No. _____
Office Address Augusta, Kansas 67010
Character of Well (Completed as Oil, Gas or Dry Hole) _____



Locate well correctly on above
Section Plat

Date Well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 7/31/79 _____ 19____
Plugging completed 8/13/79 _____ 19____
Reason for abandonment of well or producing formation
_____ depleted.

If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Owens
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4862
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	326	none
				4 1/2"	4856	2595

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sanded to 4800' and ran 4 sacks cement. Shot pipe at 4010', 3805', 3610', 3410', 3285', 3175', 3035', 2900', 2790', 2690', 2585', pulled 77 joints. Squeezed hole with 8 sacks hulls, 25 sacks gel, released plug and displaced with 125 sacks 50-50 pozmix, 4% gel and 3% cc.

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KELSO CASING PULLING
CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.
R. DARRELL KELSO (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
CHASE, KANSAS

(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of August, 19 79

My commission expires _____



Margaret Melcher
Notary Public.

RECEIVED
STATE CORPORATION COMMISSION

AUG 16 1979

CONSERVATION DIVISION
Wichita, Kansas

Oil Properties Co., Inc.
 P.O. Box 335
 Andover, Kansas 67002

Seacat #1
 C NE NW Sec. 24-28S-19W
 Kiowa County, Kansas

Contractor: D. R. Lauck Oil Company, Inc.
 221 S. Broadway, Suite 400
 Wichita, Kansas 67202

Commenced: May 29, 1979
 Completed: June 7, 1979

Drillers Log

Clay	50
Sand	195
Blue Shale	290
Shale	331
Blue Shale	495
Red Bed	1125
Shale	2129
Shale & Shells	3040
Shale & Lime	4100
Lime & Shale	4300
Lime	4388
Lime & Shale	4555
Lime	4862 RTD

RECEIVED
 STATE CORPORATION COMMISSION
 JUL 30 1979
 CONSERVATION DIVISION
 Wichita, Kansas