

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

15.145.00522.0001

API NUMBER 6-28-64

LEASE NAME Seltman AB

WELL NUMBER 2

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 11 TWP. 20S RGE. 20 (E) or (W)

COUNTY Pawnee

Date Well Completed

Plugging Commenced 3-14-89

Plugging Completed 2:30 PM

LEASE OPERATOR NCRA

ADDRESS 6000 W. 10th, Great Bend, Kansas 67530

PHONE#(316) 793-7824 OPERATORS LICENSE NO. 5565

Character of Well SWD

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? District #1

Is ACO-1 filed? NA If not, is well log attached?

Producing Formation Depth to Top 4234 Bottom 4230 T.D. 4299

Show depth and class of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Depth	From	To	Size	Put in	Pulled out
				8 5/8	473	--
				5 1/2	4299	2502.35'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Bottom: Sand to 4180 & 5 sacks cement

Top: 1100 Max/600 SI, 5 hull, 20 gel, 175 cement

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Great Bend Casing Pullers, Inc. License No. 4635 CP

Address Box 768, Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Barton, ss.

Gary G. Burke

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Gary G. Burke

(Address) Box 768, Great Bend, Kansas

SUBSCRIBED AND SWORN TO before me this 15th day of March, 1989

Louella L. Mullen
 Notary Public

My Commission Expires: 1-13-90



15.145.00522.0000
 RECEIVED
 STATE CORPORATION COMMISSION
 FEB 17 1989
 CONSERVATION DIVISION
 Wichita, Kansas

DRILLER'S LOG

National Cooperative Refinery Association
 SELTMAN "B" #1 (Seltman #2)
 C NW SW Sec. 11-20-20W
 Pawnee County, Kansas

Commenced: June 20, 1964

Completed: June 28, 1964

Set 8 5/8" at 473' and cemented with
 300 sacks cement.

Set 5 1/2" at 4299' and cemented with
 100 sacks Posmix.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>
Shale	0	287
Shale, sand, shell	287	1336
Redbed	1336	1345
Anhydrite	1345	1375
Shale	1375	1710
Shale and shells	1710	2150
Shale	2150	2365
Lime and shale	2365	4025
Lime	4025	4118
Shale and lime	4118	4225
Sand and shale	4225	4243
Shale and cherty lime	4243	4304 TD

(Pipe strapped-corrected back to 4300)

I hereby certify that the correct log of the above
 captioned well as shown by the drill log

Subscribed and sworn to before me

[Signature]

 Notary Public

My commission expires March 21, 1966

 Notary Public