

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15.145.00750.0000

LEASE NAME Robinson

WELL NUMBER #1

         Ft. from S Section Line

         Ft. from E Section Line

C SE NE

SEC. 10 TWP. 20 RGE. 20W (E) or (W)

COUNTY Pawnee

Date Well Completed 7-8-64

Plugging Commenced 9-15-87

Plugging Completed 9-21-87

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR National Cooperative Refinery Assoc.

Box 6

ADDRESS Great Bend, Kansas 67530

PHONE # (316) 793-7824 OPERATORS LICENSE NO. 5565

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? Dist. #1 Dodge City, Kansas

Is ACO-1 filed?          if not, is well log attached?         

Producing Formation          Depth to Top          Bottom          T.D. 4340'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	505'	none
				5-1/2"	4300'	2567'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plugged off bottom with sand to 4190' and 5 sacks cement. Shot pipe @3394', 3201', 3000', 2800', 2567', pulled a total of 81 joints of 5-1/2" casing.

Plugged surface with 2 hulls, 15 gel, 50 cement, 10 gel, 1 hull, plug and 150 cement, 60/40 pos, 6% gel. Plugging Complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling, Inc. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso, Vice-President (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) *Mike Kelso*

Box 347

(Address) Chase, Kansas 67524

SUBSCRIBED AND SWORN TO before me this 24th day of Sept. RECEIVED 1987

STATE CORPORATION COMMISSION

Notary Public

My Commission Expires:



SEP 25 1987

CONSERVATION DIVISION Form CP-4  
Wichita, Kansas Revised 07-86

DRILLER'S LOG

National Cooperative Refinery Association  
 Robinson #1  
 C SE NE Sec. 10-20S-20W  
 Pawnee County, Kansas

Commenced: June 30, 1964


Completed: July 8, 1964

Set 8-5/8" at 505.6 with 300 sacks cement.

Set 5-1/2" at 4300' with 100 sacks cement.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>
Surface	0	465
Shale	465	508
Salt, shale and sand	508	1400
Shale	1400	2245
Shale and lime	2245	2415
Lime	2415	2600
Lime and shale	2600	3196
Limy shale	3196	3414
Lime with chalk	3414	3679
Lime	3679	4150
Lime and shale	4150	4250
Shale, sand and chert	4250	4301 TD

I hereby certify that this is a true and correct log of the above captioned well as shown by the daily drilling reports.

  
 Ralph Schuyler

Subscribed and sworn to before me this 10th day of July, 1964.

My commission expires March 21, 1966

  
 Notary Public

STATE OF KANSAS COMMISSION

AUG 28 1967

CONSULTING ENGINEER