

15.145.20513.0000


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Pawnee County, Sec. 10 Twp. 20 Rge. 20 E/W
Location as "NE/CNW1SW1" or footage from lines
C SW NE

Lease Owner George Reed
Lease Name Seltmann Well No. 1
Office Address Fourth Financial Center Suite 645
Character of Well (Completed as Oil, Gas or Dry Hole) Wichita, Ks. 67202
dry hole



Locate well correctly on above
Section Plot

Date Well completed March 19 1978
Application for plugging filed March 19 1978
Application for plugging approved March 19 1978
Plugging commenced March 19 1978
Plugging completed 3:40 P. M. March 19 1978
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation Depth to top Bottom Total Depth of Well 4310'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from feet to
feet for each plug set.

Filled hole w/mud, pumped 70 sx cement thru open end drill pipe at 550'
Mud to 240' pumped 20 sx thru open end drill pipe,
Mud to 40', 1/2 sx Halls & wood plug for solid bridge. Pumped 10 sx
to surface, 2 sx in rathole. Used 50/50 Pozmix, 2% Gel, 3% CC

RECEIVED
STATE CORPORATION COMMISSION

MAR 22 1978

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton CONSERVATION DIVISION
Wichita, Kansas

STATE OF Kansas COUNTY OF Barton, ss.
Gary Bagby (employee of owner) or ~~owner~~ operator

of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) Gary Bagby
Gary Bagby Sterling, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of March, 1978

BESSIE M. DEWERFF
STATE NOTARY PUBLIC
BARTON COUNTY, KANSAS
My commission expires PPT. EXP. 5-20-81

Bessie M. Dewerff
Bessie M. Dewerff Notary Public.

DRILLERS WELL LOG

L. D. DRILLING COMPANY - CONTRACTOR

GEORGE REED - OPERATOR

SELTMAN# 1
C SW NE 10-20-20
PAWNEE COUNTY, KANSAS

ELEV. 2218 KB
T. D. 4310'

COMMENCED: 3-11-78
COMPLETED: 3-19-78

CASING

8-5/8" set at 297'

CEMENT

W/200 'sx 50/50 Pozmix, 2% Gel, 3% CC

FORMATION

Surface soil & clay
Shale & sand, red bed
Dakota sand
Red Beds
Anhydrite
Shale & Shells
Shale & Lime
Lime & Shale
Shale (Heebner)
Lime & Shale
Shale (Douglas)
Lime & Shale
Lime, shale & sand

DEPTH

0 - 75
75 - 785
785 - 995
995 - 1365
1365 - 1395
1395 - 1950
1950 - 3025
3025 - 3682
3682 - 3686
3686 - 3700
3700 - 3720
3720 - 4250
4250 - 4310

TOPS

Dakota
Anhydrite
Heebner
Lansing
Base K/C
Fort Scott
Cherokee Shale
Cherokee sand
R.T.D.

785
1365
3682
3728
4065
4122
4192
4250
4310

RECEIVED
STATE CORPORATION COMMISSION
MAR 22 1978
CONSERVATION DIVISION
Wichita, Kansas

AFFIDAVIT

State of Kansas County of Barton

I, Gary Bagby for the L. D. DRILLING COMPANY

being first duly sworn on oath, State: That I have knowledge of the facts statements and matters herein contained and that the same are true and correct.

Gary Bagby
Gary Bagby

Subscribed and sworn to before me on this 20th day of March 1978

BESSIE M. DEWERFF
STATE NOTARY PUBLIC
BARTON COUNTY, KANSAS
MY APPT. EXP. 3-20-81

Bessie M. DeWerff
Notary Public: Bessie M. DeWerff