

STATE OF KANSAS
ATE CORPORATION COMMISSION
3 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-02-3-117

API NUMBER 15-145-21,448-0000

LEASE NAME Dechant

WELL NUMBER 1

540 Ft. from S Section Line

540 Ft. from E Section Line

SEC. 10 TWP. 20S RGE. 20W (E) or (W)

COUNTY Pawnee

Date Well Completed _____

Plugging Commenced 10-1-01

Plugging Completed 10-3-01

LEASE OPERATOR Palomino Petroleum, Inc.

ADDRESS 4924 SE 84th St. Newton, Kansas 67114-8827

PHONE (317) 799-1000 OPERATORS LICENSE NO. 30742

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well) NOV. 13 2001

This plugging proposal was approved on KGC WICHITA (date)

by Steve Pfeifer (KGC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4271

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	499'	None.
				5-1/2"	4263'	2800'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each side. Plugged off bottom with sand to 4180' and 5 sks. cement. Shot pipe @3000' and 2800', pulled up to 1380', pumped 50 sks. cement and 10 sks. gel, pulled up to 530', pumped 50 sks. cement, pulled to 40' and pumped 20 sks. cement, 60/40 pos. 6% gel.

Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

Name of Party Responsible for Plugging Fees: Palomino Petroleum, Inc.

State of Kansas County of Rice, ss.

Mike Kelso (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 24th day of October 2001

[Signature]
Notary Public

My Commission Expires: _____

