

Handwritten mark

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
OCT 18 1971
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Rains & Williamson Oil Co., Inc.
Complete Address 435 Page Court 220 W. Douglas Wichita, Kansas 67202
Lease Name Wagner Well No. 1
Location NW NE NE Sec. 17 Twp. 20 Rge. (E) (W) 20
County Pawnee Total Depth 4339'
Abandoned Oil Well XX Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Knight Casing Pulling
Address Box 405 Chase, Kansas License No. 436
Operation Completed: Hour 1 P. Day 16. Month 10 Year 1971

The above well was plugged as follows:

Total Depth 4339' 8 5/8 csg set at 248' cwc
5 1/2 csg set at 4338' cw 150 sk cmt.
5 1/2 csg Perf. (4331')
Filled 5 1/2 csg W/sd (4300-43398) Dumped 5 sk cmt W/dump bailer. (4260-4300)
Cutoff and recovered 3006' of 5 1/2 csg.
Pumped down 8 5/8 csg with 15 sk gel & water W/100 lbs hulls, release plug and
pumped 230 sk 50-50 poz W/6% gel by Allied Cementing Co.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo F. Massup
Well Plugging Supervisor

DATE 10-18-71
INV. NO. 4486-03