

KANSAS

## STATE CORPORATION COMMISSION

## CONSERVATION DIVISION AGENT'S REPORT STATE CORPORATION COMMISSION

RECEIVED

JAN 1 1968

CONSERVATION DIVISION  
Wichita, KansasJ. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Rains & Williamson Oil Co.

Complete Address 1425 Wichita Plaza Wichita, Kansas

Lease Name Wagner Well No. 2

Location 100' E. of C NE NE Sec. 17 Twp. 20 Rge. 20 (E) (W) X

County Pawnee Total Depth 4333

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor        Co. Tools       

Address        License No.       

Operation Completed: Hour 7:15 A Day 8 Month 1 Year 1968

## The above well was plugged as follows:

RTD 4333 8 5/8 csg set at 285' cwc 175 sc. Cementing Material 50-50 Poz W/6% gel.

Gunned pits, circulated heavy mud, set cementing plug at 660' and displaced 70 sc cem.

thru drill pipe. Heavy mud to 270' set cementing plug and displaced 20 sc cement thru

drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base

of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo F. Wainwright  
Well Plugging SupervisorDATE 1/11/68  
INV. NO. 49071-U