

KANSAS

K STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAY 28 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Chief Drilling Co., Inc.

Complete Address: Box 797 Great Bend, Kansas

Lease Name Helms Well No. 1

Location SE SE Sec. 16 Twp. 20 Rge. 20 (E) (W) X

County Pawnee Total Depth 4357

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Co. Tools

Address: _____ License No. _____

Operation Completed: Hour 3:15 A Day 26 Month 5 Year 1968

The Above well was plugged as follows:

RTD 4357' 8 5/8 csg set at 221' cwc. Cem. Mat. 100 sc 6% 50-50 poz cement.
Gunned pits, circulated heavy mud, set cementing plug at 720' and displaced 70 sc cem.
thru drill pipe. Heavy mud to 210' set cementing plug and displaced 20 sc cement thru
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base
of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

Signed: R. F. Massey
Well Plugging Supervisor

INVOICED
DATE 5/28/68
INV. NO. 7831-W