

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-081-20792-00-01
Spot: E2E2W2 Sec/Twnshp/Rge: 5-28S-32W
2623 feet from S Section Line, 2767 feet from E Section Line
Lease Name: COX Well #: 1-5
County: HASKELL Total Vertical Depth: 2825 feet

Operator License No.: 34289
Op Name: ADAMS AFFILIATES, INC.
Address: 1437 S. BOULDER, STE 930
TULSA, OK 74119

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2782	0	WITH 600 SX CMT
SURF	8.625	914		WITH 410 SX CMT

Well Type: SWD UIC Docket No: D30593.0 Date/Time to Plug: 12/14/2017 3:00 PM
Plug Co. License No.: 34059 Plug Co. Name: HURRICANE SERVICES, INC.
Proposal Rcvd. from: JENNIFER SEXTON Company: ADAMS AFFILIATES Phone: (918) 582-4242

Proposed Plugging Method: CBL SHOWS TOC @ 80'. SQUEEZE PERFS WITH 25 SX CMT. PLUG AT 1930' WITH 30 SX CMT. PLUG AT 960' WITH CMT TO SURFACE. CHCECK BACKSIDE WITH CMT TO 300 PSI.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: PARTIAL
Date/Time Plugging Completed: 12/14/2017 7:00 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

CBL SHOWS TOC @ 80'. RTIH TO 2675' & SQUEEZED PERFS WITH 25 SX CMT. 1ST PLUG AT 1942' WITH 30 SX CMT. 2ND PLUG AT 955' WITH 125 SX CMT TO 0'. PUMPED 20 SX CMT DOWN BACKSIDE & PRESSURED TO 300 PSI.

Perfs:

Top	Bot	Thru	Comments
2744	2825		

INVOICED
JAN 13 7 03 AM

Remarks: USED 60/40 POZMIX 4% GEL BY HURRICANE SERVICES.

Plugged through: TBG

District: 01

Signed Kenny M. Sullivan

(TECHNICIAN)

RECEIVED
DEC 18 2017
KCC DODGE CITY