

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-187-20699-00-01  
Spot: SWNWNENE Sec/Twnshp/Rgc: 15-29S-41W  
4896 feet from S Section Line, 1027 feet from E Section Line  
Lease Name: KENDRICK Well #: 15-2  
County: STANTON Total Vertical Depth: 6000 feet

Operator License No.: 34318  
Op Name: BEREXCO LLC  
Address: 2020 N. BRAMBLEWOOD  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3838		WITH 2 SX CMT
CIBP		5400		
COND	20	40		
DVT		3412		WITH 650 SX CMT
PROD	5.5	5999	0	WITH 1150 SX CMT
SURF	8.625	1650		WITH 700 SX CMT

Well Type: SWD UIC Docket No: D27366.0 Date/Time to Plug: 12/13/2017 9:00 AM  
Plug Co. License No.: 99974 Plug Co. Name: GLOBAL CEMENTING  
Proposal Rcvd. from: GREG KLAUS Company: BEREXCO Phone: (316) 772-8650

Proposed Plugging Method: SET CIBP @ 3850' WITH 2 SX CMT. TEST CASING TO 300 PSI. PLUG AT 1380' WITH 30 SX CMT. PERFORATE AT 650' WITH CMT TO 0'.

Plugging Proposal Received By: KENNY SULLIVAN WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 12/13/2017 4:00 PM KCC Agent: HEITH WALSH

Actual Plugging Report:

SET CIBP @ 3838' WITH 2 SX CMT. PRESSURE TEST CASING TO 300# BUT DID NOT HOLD. RTIH TO 1641' & PUMPED 30 SX CMT. PTOH. SET CIBP @ 660'. PRESSURE TESTED CASING TO 500#. PERFORATE AT 655'. PUMPED 075 BBLs WATER. PRESSURED UP TO 700#. RTIH TO 640'. 2ND PLUG AT 641' WITH 73 SX CMT. PUMPED IN TO 8 5/8" X 5 1/2" ANNULUS. PRESSURED UP TO 300# RIGHT AWAY.

Perfs:

Top	Bot	Thru	Comments
5455	5471		
4122	4160		
3890	3960		

INVOICED  
JAN 16 2018

Remarks: USED 60/40 POZMIX 4% GEL GLOBAL CEMENTING.

Plugged through: CSG

District: 01

RECEIVED  
DEC 21 2017  
KCC DODGE CITY

Signed

Heith Walsh  
SA (TECHNICIAN)