

3-14 15.145.19068.0000 89

To: 1 120230
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-Drill Completion Date 6/13/64
C SW NW, SEC. 11, T 20 S, R 20 W/EX
3300 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5565

Lease Name Seltman "A-B" Well # 1

Operator: National Cooperative Refinery Assoc.
Name & Address: 6000 West 10th
Great Bend, KS 67530

County Pawnee 139.62
Well Total Depth 4296 feet

RECEIVED
STATE CORPORATION COMMISSION
MAR 21 1989
CONSERVATION DIVISION
Wichita, Kansas

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 503

Abandoned Oil Well Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pullers License Number 4635

Address P.O. Box 768, Great Bend, KS 67530

Company to plug at: Hour: 3:15 p.m. Day: 14 Month: 3 Year: 19 89

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pullers (phone) 316-793-9711

were: 5 1/2" at 4294' PBTB 4265' Perfs at 4216-19, 4238-46'

1st plug sand back to 4165' with 5 sx cement on top of sand through dump bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 125 sx cement.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4:15 p.m. Day: 14 Month: 3 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 4165' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Casing shot at 2550' and 2430'.

Pumping pressure 0-900 psi and shut in 400 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2430' of 5 1/2" casing. (if additional description is necessary, use BACK of this form.)

INVOICED (date / observed) observe this plugging.

DATE 3-23-89

Signed Duane Rankin (TECHNICIAN)

INV. NO. 24203