

9-21-87 15.145.00750.0000

To: 1 070430
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Drill completion 7/8/64
C SE NE, SEC. 10, T 20 S, R 20 W XX
3300 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5565

Lease Name Robinson Well # 1

Operator: National Cooperative Refinery Assoc.
Name & Address: Box 6
Great Bend, KS 67530

County Pawnee 139.78

Well Total Depth 4301 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 505

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 176, Chase, KS 67524

Company to plug at: Hour: 10:45 a.m. Day: 21 Month: 9 Year: 19 87

Plugging proposal received from Clay Duntz

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 5 1/2" at 4300' PBDT 4268' Perfs at 4241-44'

1st plug sand back to 4190' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 150 sx cement.

Plugging Proposal Received by Paul Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:45 a.m. Day: 21 Month: 9 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug sanded back to 4190' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released

8 5/8" wiper plug and pumped 150 sx cement.

RECEIVED STATE CORPORATION COMMISSION

SEP 29 1987

Maximum pressure 1100 psi and shut in 600 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2600' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION
Wichita, Kansas

INVOICED
observe this plugging.

DATE 10-6-87

Signed Dan Goodson (TECHNICIAN)

INV. NO. 18393