

1 050524

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 145-20,621-0000
SE
145' W C W/2, SEC. 10, T 20 S, R 20 W/EK

1320 feet from S section line
2125 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5023

Lease Name Dechant Well # 1
County Pawnee 140.44

Operator: Kansas Petroleum, Inc.
Name & Address: 225 North Market, Suite 310
Wichita, KS 67202

Well Total Depth 4321 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 468

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050
Address Box 347, Chase, KS 67524

Company to plug at: Hour: 12:00 pm Day: 20 Month: May Year: 19 85

Plugging proposal received from Neil Peddicord
(company name) Kelso (phone) 316-938-2457
were: 4 1/2" at 4318' Perfs at 4237-47'

1st plug sand back to 4185' and dump 4 sx cement on top of sand through bailer
2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,
release 8 5/8" rubber plug and pump 125 sx cement.

Plugging Proposal Received by Paul A. Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 1:20 pm Day: 20 Month: May Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 4185' and dumped 4 sx cement on top
of sand through bailer, 2nd plug squeezed well with 3 sx hulls, 15 sx gel, 50 sx cement,
10 sx gel, 1 sack hulls and released 8 5/8" rubber plug and pumped 125 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

MAY 28 1985
5-28-1985
CONSERVATION DIVISION
Wichita, Kansas

Maximum pressure 700 psi and shut in 300 psi
Remarks: Recovered 2400' 4 1/2" casing. Used 60/40 Pozmix 2% gel 3% cc by Halliburton
(If additional description is necessary, use BACK of this form.)

Signed *Richard W. Gray*
(TECHNICIAN)

INVOICED
DATE 6-6-85
I.V. NO. 8373
observe this plugging.