

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-145-21448-00-00  
Spot: CNESWSE Sec/Twnshp/Rge: 10-20S-20W  
940 feet from S Section Line, 1650 feet from E Section Line  
Lease/Unit Name: DECHANT Well Number: 1  
County: PAWNEE Total Vertical Depth: 4171 feet

Operator License No.: 5015  
Op Name: HELLAR DRILLING COMPANY, INC.  
Address: 400 N WOODLAWN SUITE 16  
WICHITA, KS 67208

Conductor Pipe: Size feet: 8/35.56  
Surface Casing: Size 8.625 feet: 499 WITH 240 SX CMT  
Production: Size 5.5 feet: 4263 WITH 125 SX CMT  
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 10/03/2001 11:30 AM

Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC. Phone: (620) 938-2537

Proposed Plugging Method: SAND TO 4180' WITH 5 SX CMT. 1ST PLUG AT 1380' WITH 50 SX CMT & 15 SX GEL . 2ND PLUG AT 550' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: JIM HOLLAND

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 10/03/2001 1:00 PM

KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PBTD 4242'. PERFS AT 4229-33, 4231-35, 4245-47, 4248-51'. SANDED BACK TO 4180' & PUT 5 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. SPOT PLUGS THROUGH 5 1/2" CASING. 1ST PLUG AT 1380' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 530' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2800' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

Signed Stephen J. Pfeifer  
(TECHNICIAN)

RECEIVED

OCT 22 2001

KCC WICHITA

INVOICED

DATE 10-22-01

INV. NO. 200206835

OCT 08 2001

MP

Form 2/3