

1050351

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 145-21,157-0000
NE, SEC. 12, T. 20 S, R. 20 W/E
4290 feet from N SE Corner of XXX section line
825 feet from W SE Corner of XXX section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5237

Lease Name Frick Well # 4

Operator: Plano Petroleum Corp.

County Pawnee

Name & Address P. O. Box 247

Well Total Depth 4375 142.19 feet

Plano, TX 75074

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 555

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Aldebaran Drilling Co., Inc. License Number 5829

Address P. O. Box 18611, Wichita, KS 67207

Company to plug at: Hour: 12:30 pm Day: 1 Month: October Year: 1984

Plugging proposal received from Mark Guinn

(company name) Aldebaran (phone) 316-685-5372

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1420' with 50 sx cement

2nd plug at 710' with 70 sx cement

solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 15 sx cement

6th plug to circulate mouse hole with 10 sx cement

Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 2:00 pm Day: 1 Month: October Year: 1984

ACTUAL PLUGGING REPORT 1st plug at 1420' with 50 sx cement, 2nd plug at 710' with 70

sx cement, 3rd & 4th plugs - solid bridge- hulls - plug at 40' -- cement to surface

with 10 sx cement, 5th plug to circulate rat hole with 15 sx cement, 6th plug to

circulate mouse hole with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Sun

OCT 05 1984

(If additional description is necessary, use BACK of this form.)

(If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION
Wichita, Kansas

Signed Richard W. Lacey
(TECHNICIAN)

INVOICED

DATE 10-8-84

INV. NO. 4143