

1010153

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 145-21,146 .0000

SE NE NW, SEC. 12, T 20 S, R20 (W)X  
4290 feet from ~~XXX~~ SE Corner of section line  
W SE Corner of  
2870 feet from ~~XXX~~ section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6024

Lease Name Jennings Well # 1-A

Operator: S & S Oil Company

County Pawnee

Name & Address 425 State Street

Well Total Depth 4390 142.68 feet

Augusta, KS 67010

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 409

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Big Springs Drilling, Inc. License Number 5381

Address Box 8287, Munger Station 400 North Woodlawn, Suite 29, Wichita, KS 67208

Company to plug at: Hour: 4:00 am Day: 6 Month: August Year: 19 84

Plugging proposal received from Darrel Krier

(company name) Big Springs (phone) 316-681-1732

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1410' with 50 sx cement

2nd plug at 800' with 50 sx cement

3rd plug at 440' with 50 sx cement  
solid bridge

4th hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 10 sx cement

Plugging Proposal Received by \_\_\_\_\_  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 6:00 am Day: 6 Month: August Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 1410' with 50 sx cement, 2nd plug at 800' with 50 sx cement, 3rd plug at 440' with 50 sx cement, 4th & 5th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with 10 sx cement.

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Halliburton

(If additional description is necessary, use BACK of this form.)

(Client) observe this plugging.

INVOICED

DATE 8-17-84

INV. NO. 3227 26

Signed Ker Beakley  
(TECHNICIAN)

RECEIVED  
STATE CORPORATION COMMISSION

AUG 10 1984

CONSERVATION DIVISION  
Wichita, Kansas