

To: ¹ 090354
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

15.145.00514.0000
API NUMBER 15-Drill Completion Date 4/3/64
NE NE SW, SEC. 13, T 20 S, R 20 W/R
2310 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6239
Operator: Zinszer Oil Company, Inc.
Name & Address: P.O. Box 211
Hays, KS 67601

Lease Name Jennings D Well # 1
County Pawnee
Well Total Depth 4300 139.75 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 527

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Zinszer Oil Company, Inc. License Number 6239
Address P.O. Box 211, Hays, KS 67601

Company to plug at: Hour: 9:50 a.m. Day: 9 Month: 11 Year: 19 93

Plugging proposal received from Perry Henman
(company name) Zinszer Oil Company, Inc. (phone) 913-625-9448

were 4 1/2" at 4299' w/100 sx cement, PBTD 4247', Perfs at 4186-87'
1st plug hook onto 4 1/2" casing and pump in 255 sx cement,
2nd plug hook onto backside and pump in 110 sx cement.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 10:40 a.m. Day: 9 Month: 11 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug hooked onto 4 1/2" casing and pumped in 255 sx cement.
Maximum pressure 700 psi and shut in 200 psi.
2nd plug hooked onto backside and pumped in 110 sx cement.
Maximum pressure 250 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. No casing recovery.
(Additional description is necessary, use BACK of this form.)

RECEIVED
STATE CORPORATION COMMISSION
NOV 16 1993
CONSERVATION DIVISION
Wichita, Kansas

INVOICED
I (did / ~~did not~~) observe this plugging.
DATE 12-9-93
INV. NO. 39435
11-9 JAN 11 1994

Signed _____
(TECHNICIAN)