

1 090355

11-9

15.145.60754.0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Drill Completion Date 9/30/63

S/2 NW, SEC. 13, T 20 S, R 20 W/R

3300 feet from S section line

3960 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6239

Lease Name Jennings C Well # 3

Operator: Zinszer Oil Company, Inc.

County Pawnee

Name & Address: P.O. Box 211

Well Total Depth 4290 ^{139.42} feet

Hays, KS 67601

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 506

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Zinszer Oil Company, Inc. License Number 6239

Address P.O. Box 211, Hays, KS 67601

Company to plug at: Hour: 12 p.m. Day: 9 Month: 11 Year: 19 93

Plugging proposal received from Perry Henman

(company name) Zinszer Oil Company, Inc. (phone) 913-625-9448

were: 4 1/2" at 4289' w/200 sx cement, PBSD 4242', Perfs at 4183-93'

1st plug hook onto 4 1/2" casing and pump in 2 sx hulls and 250 sx cement,

2nd plug hook onto backside and pump in 115 sx cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:35 p.m. Day: 9 Month: 11 Year: 19 93.

ACTUAL PLUGGING REPORT 1st plug hooked onto 4 1/2" casing and pumped in 2 sx hulls and 250 sx cement,

Maximum pressure 550 psi and shut in 450 psi.

2nd plug hooked onto backside and pumped in 115 sx cement.

Maximum pressure 400 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. No casing recovery.

INVOICED

1 (did / observe this plugging.

DATE: 12-9-93

INV. NO. 39636

11-9 JAN 11 1994

Signed _____ (TECHNICIAN)

RECEIVED STATE CORPORATION COMMISSION NOV 16 1993 CONSERVATION DIVISION Wichita, Kansas