

To: STATE CORPORATION COMMISSION 15.145.00753.0003
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Docket #E-12,417
W/2 SW NW, SEC. 13, T 20 S, R 20 W/2
3300 feet from S section line
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6239

Lease Name Jennings C Well # 2

Operator: Zinszer Oil Company, Inc.

County Pawnee

Name & Address P.O. Box 211

Well Total Depth 4272 138.84 feet

Hays, KS 67601

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 511

Abandoned Oil Well _____ Gas Well _____ Input Well X SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Zinszer Oil Co., Inc. License Number 6239

Address P.O. Box 211, Hays, KS 67601

Company to plug at: Hour: 2:25 p.m. Day: 9 Month: 11 Year: 19 93

Plugging proposal received from Perry Henman

(company name) Zinszer Oil Co., Inc. (phone) 913-625-9448

were: 4 1/2" at 4271' w/200 sx cement, PBTD 4239', Perfs at 4180-86' (3503-3610' squeezed w/350 sx)

1st plug fill production casing with cement,

2nd plug bullhead surface pipe/casing annulus with cement from surface to anhydrite.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 3:30 p.m. Day: 9 Month: 11 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug hooked onto 4 1/2" casing and pumped in 2 sx hulls and 250 sx cement. Maximum pressure 2000 psi and shut in 300 psi.

2nd plug hooked onto backside and pumped in 115 sx cement. Maximum pressure 300 psi and shut in 225 psi.

RECEIVED STATE CORPORATION COMMISSION

NOV 16 1993

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. No casing recovery.

CONSERVATION DIVISION Wichita, Kansas

INVOICED

I (did / did not) observe this plugging.

DATE 12-9-93

Signed [Signature] (TECHNICIAN)

DIV. NO. 39433

11-9 JAN 11 1994