

1080491

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION C SE
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-145-20,990-0000
SW SE, SEC. 20, T 20 S, R 20 W&E

330 feet from S section line
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5238

Lease Name Miller AV Well # 1

Operator: Petroleum, Inc.

County Pawnee 141.70

Name & Address P. O. Box 1447

Well Total Depth 4360 feet

Great Bend, KS 67530

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 482

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Rockhold Engineering License Number 5111

Address P. O. Box 698, Great Bend, KS 67530

Company to plug at: Hour: 9:30 am Day: 28 Month: February Year: 1986

Plugging proposal received from Deacon Pulley

(company name) Rockhold (phone) 316-793-8471

were: 5 1/2" at 4359' PBTD 4345' Perfs at 4322-24'

1st plug sand back to 4270' and dump 5 sx cement on top of sand through bailer

2nd plug squeeze well with 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump 150 sx cement.

Plugging Proposal Received by Paul A. Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:30 am Day: 28 Month: February Year: 1986

ACTUAL PLUGGING REPORT 1st plug sanded back to 4270' and dumped 5 sx cement on top of sand through bailer, 2nd plug squeezed well with 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 150 sx cement.

Maximum pressure 100 psi and shut in 600 psi. Recovered 2500' 5 1/2" casing.

Remarks: Used 60/40 Pozmix 6% gel by BJ-Titan.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE MAR 04 1986

INV. NO. 12852

STATE CORPORATION COMMISSION

MAR 4 1986

CONSERVATION DIVISION
Wichita, Kansas

Signed J. H. [Signature]
(TECHNICIAN)