

1060188

TO: STATE CORPORATION COMMISSION

API NUMBER 15-145-20,860.0000
SE SW NE SEC. 17, T 20 S, R 20 W

CONSERVATION DIVISION - PLUGGING SECTION 1650 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1650 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME SHOWALTER WELL # 1

TECHNICIAN'S PLUGGING REPORT

COUNTY PAWNEE 139.72

OPERATOR LICENSE # 30601

WELL TOTAL DEPTH 4299 FEET

OPERATOR: NORTHSTAR INVESTMENTS, INC. PRODUCTION CSG: SIZE 4 1/2" @ 4296' WITH 100 SX

NAME AND 13735 PINNACLE SURFACE CASING: SIZE 8 5/8" @ 244' WITH 185 SX

ADDRESS WICHITA, KS 67230-1545

ABANDONED OIL WELL X GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR QUALITY WELL SERVICE LICENSE NUMBER 31925

ADDRESS 249 BETH DRIVE, STERLING, KS 67579

COMPANY TO PLUG AT: HOUR: 11:00 AM DAY: 03 MONTH: 01 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM RICHARD MCINTYRE

(COMPANY NAME) QUALITY WELL SERVICE (PHONE) 316-727-3410

WERE: OPEN HOLE

1ST PLUG SAND TO 4239' WITH 4 SX CEMENT. PULLED STRETCH AND ONLY HAD ONE INCH. SHOT AT 800' WOULDN'T COME. SHOT AT 547' WOULDN'T COME LOOSE. PUMPED 80 SX CEMENT. WAITED 2 1/2 HOURS. SHOT AT 280' PUMPED 40 SX CEMENT. PULLED CASING OUT OF HOLE AND TOPPED OFF WITH 20 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY MIKE MAIER

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 4:00 PM DAY: 03 MONTH: 01 YEAR: 2000

ACTUAL PLUGGING REPORT

1ST PLUG SAND TO 4239' WITH 4 SX CEMENT. PULLED STRETCH AND ONLY HAD ONE INCH. SHOT AT 800' WOULDN'T COME. SHOT AT 547' WOULDN'T COME LOOSE. PUMPED 80 SX CEMENT. WAITED 2 1/2 HOURS. SHOT AT 280' PUMPED 40 SX CEMENT. PULLED CASING OUT OF HOLE AND TOPPED OFF WITH 20 SX CEMENT.

RECEIVED

STATE CORPORATION COMMISSION

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 280' OF 4 1/2" CASING. 1-12-2000

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM)

I (DID) OBSERVE THIS PLUGGING.

INVOICED
DATE 1/13/00

SIGNED Michael J. Maier CONSERVATION DIVISION (TECHNICIAN) FORM CP-273, Kansas

INV. NO. 06443