

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

Pawnee County, Sec. 12 Twp. 20 Rge. (E) 20(W)

Location as "NE/CNW/SW" or footage from lines 330' N. & 330' E. of SW Cor.

Lease Owner Cities Service Oil Company

Lease Name Jennings Well No. 1

Office Address Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed March 23, 19 54

Application for plugging filed March 23, 19 54

Application for plugging approved March 23, 19 54

Plugging commenced March 23, 19 54

Plugging completed March 23, 19 54

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives

Producing formation Mississippi Depth to top 4288 Bottom 4303 Total Depth of Well 4303 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	433'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

4303-300', heavy mud.

300-240', wood plug, hulls and 20 sacks cement.

240-40', mud.

40' to base of cellar, hulls, wood plug and 10 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Brack Drilling Co., Inc.

Address 309-10 Brown Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Barton, ss. V. M. Conover (employee of owner) or (~~owner or operator~~) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) V. M. Conover


Box 751, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 24th day of March, 19 54

W. J. Smith
Notary Public.

My commission expires March 12, 1955.

24-7966-8 3-53-20M



MAR 27 1954

CONSERVATION DIVISION
Wichita, Kansas

3-27-1954

WELL RECORD

Company Cities Service Oil Co. Well No. 1 Farm Jennings
 Location 330' North and 330' East of SW Cor. Sec. 12 T. 20 R. 20W
 Elevation 2212 (2209 Gr.) County Pawnee State Kansas
 Drlg. Comm. March 8, 1954 Contractor Ben F. Brack Oil Co., Inc.
 Drlg. Comp. March 23, 1954 Acid None
 T. D. 4303' Initial Prod. Dry Hole - P. & A. 3-23-54.

GASING RECORD:

8-5/8" @ 533' cas. 300 ex cement

FORMATION RECORD:

clay & shale	0-110
shale & sand	290
shale & shells	300
shale, sand & pyrite	534
shale & shells	600
red bed & shale	780
sand	1030
shale & shells	1290
anhydrite	1325
shale & shells	1625
salt	1675
shale & shells	1900
shale	2140
lime & shale	2350
lime	2695
lime & shale	3045
shale & lime	3132
lime	3215
lime & shale	3325
shale & shells	3405
lime & shale	3550
shale & lime	3645
lime & shale	3715
lime	4197
lime & sand	4249
lime, shale & sand	4277
lime & chert	4303 T. D.

Hebner	3673'
Dodge	3695'
Landing	3724'
Basal Pennsylvania Sand	4212'
Mississippi	4288'
Penetration	15'
Total Depth	4303'

Drill Stem Test 4210-24, open 1 hr., recovered 20' mud with specks oil, 30' watery mud and 120' muddy salt water; B. H. P. 795#/30 mins.

Drill Stem Test 4237-49, open 1 hr., recovered 25' mud and 480' slightly muddy salt water; B. H. P. 1320#/30 mins.

SLOPE TESTS (TOTCO):

500'	0°
1000'	0°
1500'	0°
2000'	1°
2500'	1 1/2°
3000'	1°
3534'	1-3/4°
4000'	2°

PLUGGING
 FILE SEC 12 T 20 R 20 W
 BOOK PAGE 22 LINE 31

REC
 STATE OF KANSAS
 CONSERVATION DIVISION
 Wichita, Kansas