

15.145.00753.0003

API NUMBER 15-145-01358-0003

LEASE NAME Jennings C

WELL NUMBER #2

3300 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 13 TWP. 20 RGE. 20 (S) or (W)

COUNTY Pawnee

Date Well Completed 6/19/63

Plugging Commenced 11/09/93

Plugging Completed 11/09/93

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Zinszer Oil Company, Inc.

ADDRESS P.O. Box 211, Hays, Kansas 67601

PHONE# (913) 625-9448 OPERATORS LICENSE NO. 6239

Character of Well Oil / Input

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on Before 11/09/93 (date)

by Steve Middleton and Steve Durrant (KCC District Agent's Name).

Is ACO-1 filed? no if not, is well log attached? yes

Producing Formation Cherokee Depth to Top 4180 Bottom 4186 T.O. 4272

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Cherokee	Oil	511	5	8 5/8	506	none
		4271	0	4 1/2	4271	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set.  
Pumped 240sx 40%poz 60% standard 6% gel with 100# hulls in first part down  
4 1/2" casing 1300# max psi, 500# SIP, hook up to annulus and pumped 120sx  
40%poz 60% standard 6%gel, 400# max psi, 225# SIP.

Name of Plugging Contractor Halliburton License No. \_\_\_\_\_

Address P.O. Box 428, Hays, Kansas 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Zinszer Oil Company, Inc

STATE OF Kansas COUNTY OF Ellis, ss.

Perry S. Henman (Employee of Operator) ~~XXXXXXXXXX~~

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P.O. Box 211, Hays, KS 67601

SUBSCRIBED AND SWORN TO before me this 17<sup>th</sup> day of January, 1994

My Commission Expires: August 24, 1994

Notary Public  
STATE CORPORATION COMMISSION

NOTARY PUBLIC - State of Kansas  
ROBERT J. SCHUBI  
My Appt. Exp. 8/24/94

JAN 19 1994  
Revised 05-88

CONSERVATION DIVISION  
Wichita, Kansas

# WELL RECORD

15.145.00753.0000

Company Wiles Service Oil Co., et al Well No. #2 Farm Jennings "C"  
 Location 1980' South and 330' East of NW Corner Sec. 13 T. 20 R. 20W  
2212 K.B., 2209 D.F.,  
 Elevation 2204 Gr. County Pawnee State Kansas  
 Initial Prod. 143 oil, no water, 24 hours, 7-17-63. Contractor Peel Bros., Inc.  
 Acid None Drig. Comm. 6-19-63  
 T. D. 4272'. F.B.T.D. 4239.5' Drig. Comp. 7-6-63

**CASING RECORD:**

8-5/8" at 511' with 300 sacks cement.  
 4-1/2" at 4272' with 200 sacks cement.

**FORMATION RECORD:**

clay and streaks sand	0-20
shale and shells	320
shale and sand	395
shale and streaks pyrite	511
shale	560
red bed and shells	625
anhydrite	710
shale and shells	770
sand	980
shale and shells	1350
Anhydrite	1382
shale and shells	2110
shale and lime	2319
lime and shale	2508
shale and lime	2630
lime and shale	2700
shale and lime	2810
lime and shale	2940
shale and lime	3020
lime and shale	3530
lime	436
lime and shale	4180
Cored lime, shale & sand (rec. 30')	4210
Cored shale, sand & chert (rec. 46')	4256
chert and lime	4280

4280 Rotary T.D.=4272 corrected to top of 4 1/2" casing at ground level.

Data corrected by P.F.C. log from top of 4 1/2" casing at ground level, elevation 2204'.

Heiner	2643
Toronto	3582
Lansing	3690
Base Kansas City	4062
Sherokee Shale	4150
Sherokee Sand	4180
Mississippi	4241
Pen.	31'
T.D.	4272

Cleaned-out to 4239 1/2'.  
 3880' water load in hole.  
 Perforated 24 shots 4180-86.

**SLOPE TESTS (SYFO):**

500'	- 1 1/2"
1000'	- 0"
1500'	- 1 1/2"
2000'	- 1 1/2"
2500'	- 1 1/2"
3000'	- 1 1/2"
3500'	- 1 1/2"

4180  
 2212  
 65

RECEIVED  
 STATE CORPORATION COMMISSION

JAN 19 1994

CONSERVATION DIVISION  
 Wichita, Kansas

COPY