


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Pawnee County, Sec. 15 Twp. 20S Rge. 20W NE/W  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines  
SW/4 SE/4 SW/4

Lease Owner ETK River Oil Company  
Lease Name Dick Well No. 1  
Office Address Suite 300 Farmers & Bankers Bldg., Wichita, Ks.  
Character of Well (Completed as Oil, Gas or Dry Hole) D & A



Locate well correctly on above  
Section Plat

Date Well completed March 2, 1978  
Application for plugging filed March 2, 1978  
Application for plugging approved March 2, 1978  
Plugging commenced March 2, 1978  
Plugging completed March 2, 1978  
Reason for abandonment of well or producing formation D & A

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or  
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo F. Massey  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4,310  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	364.61'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugged hole @ 550' w/70 sx cement  
@ 300' w/20 sx cement  
@ 40' w/10 sx cement

RECEIVED  
STATE CORPORATION COMMISSION

MAR 09 1978

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Red Tiger Drilling Company  
1720 KSB&T Building, Wichita, Kansas 67202

STATE OF Kansas COUNTY OF Sedgwick, ss. contractor  
Gloria Fawcett (employee of ~~xxxxxx~~)


of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Gloria Fawcett  
1720 KSB&T Building, Wichita, Kansas 67202  
(Address)

SUBSCRIBED AND SWORN TO before me this 7th day of March, 1978.

Joyce A. Hagermann  
Notary Public.

My commission expires \_\_\_\_\_



DRILLERS LOG

No. 1 Dick

CASING RECORD: 8 5/8" @ 372' w/235 sx cement

COMPANY: Elk River Oil Company

CONTRACTOR: Red Tiger Drilling Company

COMMENCED: February 19, 1978

COMPLETED: March 2, 1978

DESCRIPTION: SW/4 SE/4 SW/4  
Sec. 15-T20S-R20W  
Pawnee County, Kansas

TOTAL DEPTH: 4,310'

ELEVATION: 2,219' KB

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Clay, Sand, Shale	0	130	
Shale	130	800	
Sand	800	1000	
Shale	1000	1356	
Anhydrite	1356	1387	
Lime & Shale	1387	2070	
Shale & Lime	2070	2445	
Lime	2445	2550	
Lime & Shale	2550	2985	
Shale & Lime	2985	3125	
Lime & Shale	3125	3480	
Shale & Lime	3480	3665	
Lime	3665	4225	
Lime & Shale	4225	4310	
RTD		4310	

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 09 1978  
G. S. WAGNER, Notary Public  
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Gloria Fawcett  
Gloria Fawcett

Subscribed and sworn to before me this 7th day of March, 1978.

Joyce A. Hagermann  
Notary Public

