


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Pawnee County, Sec. 14 Twp. 20S Rge. 20 (E) (W)

Location as "NE/CNW/SW" or footage from lines NW NW SE
Lease Owner Parker Petroleum Company, Inc.
Lease Name Risse Well No. 1
Office Address P. O. Drawer 791 - Ponca City, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 9-1 1956
Application for plugging filed 9-1 1956
Application for plugging approved 9-1 1956
Plugging commenced 9-1 1956
Plugging completed 9-1 1956
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well R. M. Brundege
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4366 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Heebner	No Show	3684		10 3/4	531'	
Lansing	"	3732				
Cherokee	"	4173				
Mississippi	"	4329				

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Hole filled with heavy rotary mud. Bottom plug set @ 330' cemented with 15 sacks cement.
Hole filled with mud and hulls to 35'. Plug set with 15 sacks. Hole plugged 2 A.M.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Johnie S. Carter Drilling Company
Address 406 C. A. Johnson Building - Denver 2, Colorado

STATE OF Kansas, COUNTY OF Butler
Joe W. Cain - General Supt. (employee of owner) of J. C. Smitherman Drilling Company of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Joe W. Cain
Box 627 - Augusta, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 13th day of September, 1956

Ruth H. Carter
Notary Public.

My commission expires October 23, 1958.

PLUGGING
FILE SEC. 14 T. 20 R. 20W
BOOK PAGE 96 LINE 1

RISSE #1

Company: L. C. Smitherman Drlg. Co.

Contractor: Johnie S. Carter Drlg. Co.

Commenced: 8/11/56

Completed: 9/1/56

T.D. 4366'

Init. Prod. D. & A.

Location: NW NW SE Sec. 14-20S-20W
Pawnee County, Kansas

Elevation:


Casing: 10-3/4" - 531.14 cemented
with 325 sacks.Figures Bottoms of Formations:

Depth

0 - 190	Shale and sandy shale
190 - 530	Surface clay and shale
530 - 552	Blue shale
552 - 600	Blue shale and gyp
600 - 800	Red Bed
800 - 1035	Sand
1035 - 1360	Red Bed and shale
1360 - 1390	Anhydrite
1390 - 2035	Shale and shells
2035 - 2200	Shale
2200 - 2300	Shale and Lime
2300 - 2485	Lime and shale
2485 - 2605	Lime
2605 - 2780	Shale and Lime
2780 - 3025	Lime and Shale
3025 - 3140	Shale
3140 - 3275	Lime and shale
3275 - 3330	Shale with lime streaks
3330 - 3415	Lime and shale
3415 - 3535	Sandy shale and lime
3535 - 3710	Lime and shale
3710 - 3788	Lime
3788 - 3826	Cherty Lime
3826 - 3910	Lime
3910 - 3945	Lime and shale
3945 - 4185	Lime
4185 - 4265	Cherokee shale
4265 - 4366	Lime and shale
4366 - R.T.D.	

We hereby certify the above and foregoing to be a true and correct copy of the log on the Risse #1, located in the NW NW Se Sec. 14-20S-20W Pawnee County, Kansas.

JOHNIE S. CARTER DRLG. CO.



Subscribed and sworn to before me this 5th day of September, 1956.



Notary Public

My commission expires August 10, 1959.

PLUGGING
FILE SEC. 14 T. 20 R. 20W
BOOK PAGE 96 LINE 1