


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Pawnee County. Sec. 14 Twp. 20 Rge. 20 (E)W. (W)
Location as "NE/CNW/SW" or footage from lines 330' S., 330' W. of NE Cor.
Lease Owner Cities Service Oil Company
Lease Name Risse "A" Well No. 1-W
Office Address Box 308, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Injection
Date well completed August 11 19 61
Application for plugging filed January 6 19 66
Application for plugging approved January 10 19 66
Plugging commenced February 22 19 66
Plugging completed February 25 19 66
Reason for abandonment of well or producing formation No longer needed for injection purposes.
If a producing well is abandoned, date of last production - 19 -
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Leiker
Producing formation Basal Penn. Depth to top 4170 Bottom 4182 Total Depth of Well 4540 Feet
Show depth and thickness of all water, oil and gas formations. 4209 4216 P. B. T. D. 4191 Feet

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	412'	None
				5-1/2"	4400'	2634'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

4191-4160', sand.
4160-4110', 5 sx cement.
4110- 480', mud and rock bridge.
480- 420', 20 sx cement.
420- 200', mud.
200- 140', 20 sx cement
140- 40', mud.
40' - base cellar, 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

MAR 8 1966

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Knight Casing Pulling Company
Address Chase, Kansas

STATE OF Kansas, COUNTY OF Pawnee, ss.
W. J. Devaney (employee of owner) ~~owner or operator~~ of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. J. Devaney
Box 308, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 1st day of March, 19 66

My commission expires Dec. 6, 1966

Chas. McFarland
Notary Public.

