

15.145.20990.0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-145-20,990

LEASE NAME Miller "AV"

WELL NUMBER #1

SPOT LOCATION SE SW SE

SEC. 20 TWP. 20 RGE. 20 (E) or (W)

COUNTY Pawnee

Date Well Completed _____

Plugging Commenced 2-22-86

Plugging Completed 2-28-86

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Petroleum Inc.

ADDRESS Box 1447, Great Bend, Ks. 67530

PHONE # (316) 793-8968 OPERATORS LICENSE NO. 5238

Character of Well oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? One (1)

Is ACO-1 filed? _____ If not, is well log attached? With application

Producing formation _____ Depth to top _____ bottom _____ T.D. 4360'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	482'	None
				5-1/2"	4359'	2,470.19'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Dumped sand to 4270' and 5 sacks cement. Shot casing at 3800', 3300', 2800' and 2500'. Pulled 70 joints of 5-1/2" casing. B.J. Titan squeezed well with 2 sacks hulls, 15 sacks gel, 50 sacks cement, 10 sacks gel, 1 sack hulls, released plug and pumped 150 sacks 60/40 pozmix cement with 6% added gel, Maximum pressure was 700 psi and shutin 600 psi.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Gt. Bend, Ks. 67530

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold (employee of operator) or
(operator) of above-described well, being first duly sworn on oath, says: That
I have knowledge of the facts, statements, and matters herein contained and
the log of the above-described well as filed that the same are true and
correct, so help me God.

(Signature) James W. Rockhold
(Address) James W. Rockhold
Box 698, Gt. Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 3rd day of March, 1986

STATE NOTARY PUBLIC
IONA M. LEATHERMAN
Barton County, Kansas
My Appt. Exp. 9-26-87

Iona M. Leatherman
STATE CORPORATION COMMISSION PUBLIC

My Commission expires: _____

MAR 4 1986

CONSERVATION DIVISION
Wichita, Kansas

Form CP-4
Revised 11-85