


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

Pawnee County. Sec. 17 Twp. 20 Rge. 20 (E) W (W)

Location as "NE/CNW/SW" or footage from lines NW SE NW
Lease Owner O. A. Sutton
Lease Name Wagner Well No. 2
Office Address 407 Insurance Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry
Date well completed 7-13 19 59
Application for plugging filed 7-13 19 59
Application for plugging approved 7-13 19 59
Plugging commenced 7-13 19 59
Plugging completed 7-13 19 59
Reason for abandonment of well or producing formation Dry

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19 ____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4450 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	252'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled with heavy mud from 4450 to 240'.
Set plug # 1 at 240'. Mixed 1/4 sack hulls
and 20 sacks cement. Filled with heavy mud
180' up to 30'. Set plug # 2 at 30'. Mixed 1/4
sack hulls and 24 sacks cement. Mixed 5 sacks
cement in top of rat hole.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Renfro Drilling Company
Address 316 Insurance Building, Wichita, Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Handwritten Signature]

(Address) _____

SUBSCRIBED AND SWORN TO before me this 15th day of July, 19 59

My commission expires November 7, 1961 Marilyn E. Fox Notary Public.

PLUGGING
FILE SEC. 17 T. 20 R. 20W
BOOK PAGE 51 LINE 42

RECEIVED
STATE CORP. COMMISSION

JUL 17 1959

CONSERVATION DIVISION
Wichita, Kansas

O. A. Sutton, Wagner #2
 NW SE NW Sec. 17-20S-20W
 Pawnee County, Kansas

Commenced - June 29, 1959
 Completed - July 13, 1959
 Casing - 252' of 8-5/8" csg. w/200 sax HA5
 Elevation - 2205 KB

DRILLERS LOG

0 - 252	Surface
252 - 480	Shale and red bed
480 - 940	Shale and red bed
940 - 1397	Shale and red bed
1397 - 1525	Lime and shale
1525 - 1648	Shale and lime
1648 - 2000	Shale and lime
2000 - 2190	Lime and shale
2190 - 2309	Shale and lime
2309 - 2425	Lime and shale
2425 - 2520	Lime
2520 - 2612	Lime and shale
2612 - 2695	Lime and shale
2695 - 2815	Lime
2815 - 2933	Lime and shale
2933 - 3050	Lime and shale
3050 - 3150	Lime and shale
3150 - 3252	Lime and shale
3252 - 3362	Lime and shale
3362 - 3465	Lime and shale
3465 - 3547	Lime
3547 - 3740	Lime
3740 - 3834	Lime
3834 - 3875	Lime
3875 - 3925	Lime
3925 - 3981	Lime
3981 - 4040	Lime
4040 - 4087	Lime
4087 - 4234	Lime
4234 - 4299	Lime
4299 - 4335	Lime
4335 - 4352	Lime and shale
4352 - 4375	Miss.
4375 - 4408	Miss. lime and chert
4408 - 4441	Miss.
4441 - 4450	Miss.
4450 -	Rotary Total Depth

STATE OF KANSAS)
) SS
 SEDGWICK COUNTY)

I, the undersigned, being duly sworn on oath, state that the above Drillers Log is true and correct to the best of my knowledge and belief and according to the records of this office.

RENFRO DRILLING CO.

By Henry D. Fickon

Subscribed and sworn to before me this 16th day of July, 1959.

Lorraine Shullcutt
 Notary Public

My commission expires:
 June 1, 1960.

PLUGGING
 FILE SEC. 17 T. 20 R. 20W
 BOOK PAGE 51 LINE 42