


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

WELL PLUGGING RECORD

Pawnee County, Sec. 17 Twp. 20 Rge. 20 (E) W (W)

Location as "NE/CNW%SW%" or footage from lines SE SE NW  
Lease Owner Morgenstern Oil Operations  
Lease Name Wagner Well No. 1  
Office Address Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole)  
Date well completed 19  
Application for plugging filed 19  
Application for plugging approved 19  
Plugging commenced 9-16-61 19  
Plugging completed 9-25-61 19  
Reason for abandonment of well or producing formation Depleted



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Fred Hample  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4620 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	464'	None
				5-1/2"	4400'	3331'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Checked hole to 4359', sanded to 4315' and dumped 5 sacks of cement @ 4315' with dump bailer. Pulled 5 1/2" casing. Mudded hole to 310', set 10' rock bridge to 300' and ran 20 sacks of cement @ 300'. Mudded to 40', set 10' rock bridge to 30' and ran 10 sacks of cement to base of cellar.

RECEIVED  
STATE CORPORATION COMMISSION

PLUGGING COMPLETE.

OCT 16 1961

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor KNIGHT CASING PULLING COMPANY  
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.  
Noel J. Knight (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight  
Chase, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 26th day of September, 1961

Milton J. Volin  
Notary Public.

My commission expires May 20, 1964



WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas


15.145.00272.0000

Company O. A. SUTTON  
Farm Wagner No. 1

SEC. 17 T. 20 R.20W  
SE SE NW

Total Depth. 4620'  
Comm. 3-30-57 Comp. 4-24-57  
Shot or Treated.  
Contractor. Murfin Drilling Company  
Issued. 3-8-58

County Pawnee  
KANSAS



Elevation. 2185' KB

Production. 95 BOPD

CASING:

8 454' cem w/250 sx

Figures indicate Bottom of Formations.

WOC	462
shale-shells	630
red bed -shale	800
sand	1010
red bed	1360
Anhydrite	1395
shale-shells	1405
red rock shale-shells	1790
salt-shale	1950
shale-lime shells	2015
lime-shale	3480
lime	3595
lime-shale	3764
lime	4151
lime-shale	4225
lime	4248
lime shale	4280
lime-shale-sand	4305
lime-sand-chert	4324
Mississippi	4337
Mississippi-lime	4411
Chert-shale Dolomite	4534
Dolomite-chert shale	4583
Arbuckle	4620-RTD
Total Depth	

TOPS:	
Anhydrite	1360
Topeka	3450
Heebner	3690
Toronto	3710
Lansing	3741
Mississippi (Scout)	4325
Simpson (Scout)	4570
Arbuckle (Scout)	4583

DST #1, 4210-48, Open 1 hr. Rec. 8' drlg.  
mud. BHP 0.

DST #2, 4327-42, 1 hr. Rec. 190' gas in  
drill pipe - 45' ocm 840' free d  
oil, 60' wtr. BHP 1228#.

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 5 1961  
CONSERVATION DIVISION  
Wichita, Kansas