


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD

Pawnee County, Sec. 17 Twp. 20 Rge. 20 (E) W (W)

Location as "NE/CNW/SW" or footage from lines NE NE SW
Lease Owner Morgenstern Oil Operations.
Lease Name Dickson Well No. 1
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 9-25-61 _____ 19____
Plugging completed 9-28-61 _____ 19____
Reason for abandonment of well or producing formation Depleted.

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Fred Hample
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4358 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10"	263'	None
				5-1/2"	4357'	3451'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole to 4255', sanded to 3990' and dumped 5 sacks of cement @ 3990' with dump bailer. Pulled 5 1/2" casing. Mudded hole to 250', set 10' rock bridge to 240' and ran 20 sacks of cement @ 240'. Mudded to 35', set rock bridge and ran 10 sacks of cement to base of cellar.

PLUGGING COMPLETE.

STATE CORPORATION COMMISSION
OCT 16 1961

CONSERVATION DIVISION
Wichita, Kansas

10-16-1961

Name of Plugging Contractor Knight Casing Pulling Company
Address Chase, Kansas

STATE OF Kansas COUNTY OF Rice, ss.
Noel J. Knight (employee of owner) or ~~owner~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 29th day of September, 1961

Milton J. Volin
Notary Public.

My commission expires May 20, 1964



WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


COPY

Company- NATURAL GAS & OIL CO.
Farm- Dixon No. 1

SEC. 17 T. 20 R. 20W
NE NE SW

Total Depth. 4358'
Comm. 3-4-58 Comp. 3-19-58
Shot or Treated.
Contractor. Capitt Drilling, Inc.
Issued. 5-31-58

County Pawnee
KANSAS



Elevation. 2198' RB

Production, Dry

CASING:

10 3/4" 263' cem w/225 sx.
5 1/2" 4357' cem w/100 sx.

Figures Indicate Bottom of Formations.

clay & shells	185
shale & lime strks	265
shale, red bed & lime streaks	1070
shale, red bed	1368
Anhydrite	1405
shale	1900
shale & lime	2253
lime	2741
lime & shale	2820
shale & shells	2935
lime & shale	3050
shale & lime	3097
shale	3120
shale & lime strks	3212
lime	3250
lime & shale strks	3370
shale & lime	3470
lime & shale	3633
lime	4333
chert	4354
lime & chert	4358 RTD
Total Depth	

RECEIVED
STATE CORPORATION COMMISSION
SEP 27 1961
CONSERVATION DIVISION
Wichita, Kansas

TOPS:	SAMPLE	LANE WELLS
Heebner Shale	3704	3702
Lansing-Kansas City	3754	3754
Base Pawnee Lm.	4229	4228
Base Ft. Scott	4264	4262
Mississippi Chat	4333	4332

DST 4334-40, open 1 hr, rec. 13' mud, IBHP 923#,
SI 15 min; BHP 815#.

4336-68, open 1 1/2 hrs, fair blow throughout
rec. 60' OCM, 180' MO, FFP 135#, BHP 1310#.
SI 30 min.

Perf. 72 bullets from 4338-4348, no show.
Fraced down casing w/3000 G T-0 and 3000# sand.
24 holes 4350-4358, 250 Gal mud sol.
Perf. 4355-51 with 23 holes.