


STATE OF KANSAS
 STATE CORPORATION COMMISSION

Give All Information Completely
 Make Required Affidavit
 Mail or Deliver Report to:
 Conservation Division
 State Corporation Commission
 212 No. Market
 Wichita, Kansas 67202

WELL PLUGGING RECORD



Locate well correctly on above Section Flat

Pawnee County, Sec. 17 Twp. 20 Rge. 20 (E) (W)
 Location as "NE/CNW/SW" or footage from lines _____
 Lease Owner Rains & Williamson Oil Co.
 Lease Name Wagner #1 Well No. _____
 Office Address Wichita, Kansas 67202
 Character of Well (completed as Oil, Gas or Dry Hole) _____
 Date well completed _____ 19____
 Application for plugging filed _____ 19____
 Application for plugging approved _____ 19____
 Plugging commenced 10/8/71 _____ 19____
 Plugging completed 10/16/71 _____ 19____
 Reason for abandonment of well or producing formation depleted.
 If a producing well is abandoned, date of last production _____ 19____
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Massey
 Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4339 Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	248	none
				5 1/2"	4338	3010'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked bottom, ran sand to 4300' and dumped 5 sacks of cement.
 Shot pipe at 3430', worked pipe to 26" tension. Checked hole, mud came up hole to 2100', pumped 210 barrels water. Shot pipe at 3335', 3238', 3145', 3040', pulled 95 joints. Allied pumped 1 sack hulls, 15 sacks gel and 130 sacks of cement.

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)
 Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.
 Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.
NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Noel Knight*
CHASE, KANSAS
 (Address)

18th day of October, 1971

Subscribed and sworn to before me this _____ day of _____, 1971.

 My commission expires _____

Margaret Melcher
 Notary Public.

ROTARY DRILLING LOG

Operator: Rains & Williamson
Oil Co., Inc.
WAGNER #1
NW NE NE Section 17-20S-20W
Pawnee County, Kansas

Contractor: Rains & Williamson
Oil Co., Inc.
Commenced: 7-7-71
Completed: 7-16-71
Casing: 8-5/8"/248'/150 sacks
5-1/2"/4338'/150 sacks

Formations

Surface Clay	40'
Shale	800'
Sand	995'
Shale	1360'
Anhydrite	1388'
Shale	1800'
Shale and Lime	2300'
Lime and Shale	2430'
Lime	2620'
Lime and Shale	3405'
Lime	3555'
Lime and Shale	3759'
Kansas City	3895'
Lime	4309'
Mississippi	4339'
Rotary Total Depth	4339'

RECEIVED
STATE CORPORATION COMMISSION
JUL 20 1972
CONSERVATION DIVISION
Wichita, Kansas

We certify the above log is true and correct, to the best of our knowledge and belief.

RAINS & WILLIAMSON OIL CO., INC.

Wilson Rains
Wilson Rains

Subscribed and sworn to before me, a Notary Public, within and for the State of Kansas, County of Sedgwick, this 3 day of August, 1971.

Jeanine Durand
Jeanine Durand Notary Public

My Commission Expires: 3-31-74

