

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

15.145.20323.0000

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
FEB 27 1974
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Aspen Drilling Co.

Complete Address Box 783 Great Bend, Kansas

Lease Name Buckman Well No. 1-14

Location SE SW Sec. 14 Twp. 20 Rge. (E) (W) 18

County Pawnee Total Depth 2230'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor DAMac Drlg.

Address Wichita, Kansas License No.

Operation Completed: Hour 8 P Day 23 Month 2 Year 1974

The above well was plugged as follows:

RTD 2230' 8 5/8 csg set at 403' cwc

Gunned pits, circulated heavy mud, set cementing plug at 435' and displaced 50 sk
cmt thru drill pipe. Heavy mud to 240' set cementing plug and displaced 25 sk cmt
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo F. Massey
Well Plugging Supervisor

INVOICED

DATE 2/27/74

INV. NO. 8660-10