

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 -097-20,539-0000 (of this well)

Operator's Full Name Oil Properties Co. Inc.

Complete Address Box 335-Andover, Ks. 67002

Lease Name Seacat Well No. 1

Location C NE NW Sec. 24 Twp. 28 Rge. 19 (E) (W) X

County Kiowa Total Depth 4862

Abandoned Oil Well X Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Kelso Casing Pulling

Address Box 176-Chase, Ks. 67524 License No. 683

Operation Completed: Hour 11:30 Am. Day 13 Month 8 Year 1979

The above well was plugged as follows:

326' 8 5/8" casing w/275 sax cement. 4 1/2" casing set at 4856' w/100  
sax cement. Sand back to 4800'-Top sand w/4 sax mixed cement w/ dump  
bailer. Pull 2585' 4 1/2" casing. Allied mixed & pumped 8 sax hulls-  
25 sax gel-Release plug-Mixed & pumped 125 sax 50/50 posmix cement  
w/4% gel & 3% cc to top of casing. Shut in w/ "0" pressure.

I hereby certify that the above well was plugged as herein stated.

**INVOICED**

DATE 8-16-79

INV. NO. 0250-W

Signed: [Signature]  
Well Plugging Supervisor

WICHITA DIVISION  
Wichita, Kansas

RECEIVED  
STATE CORPORATION COMMISSION

AUG 15 1979

8-15-79