


AFFIDAVIT AND COMPLETION FORM

ACO-1

This form must be filed in triplicate with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within five days after the completion of the well, regardless of how the well was completed. Circle one: Oil, gas, dry, SWD, OWWO, injection. Please type. Complete ALL sections. Applications must be filed for dual completion, commingling, salt water disposal and injection. Attach wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.) KCC#-(316) 263-3238.

OPERATOR Anador Resources, Inc. API NO. 145-20834
 ADDRESS 5700 S. Quebec Suite 320 COUNTY Pawnee
Englewood, Colorado 80111 FIELD X Wildcat ASHVALEY
 **CONTACT PERSON David S. Dudzik LEASE Haas
 PHONE 303-741-2886 PROD. FORMATION Krider
 PURCHASER _____ WELL NO. 1-20
 ADDRESS _____ WELL LOCATION C SE
 _____ 1320 Ft. from South Line and
 _____ 1320 Ft. from East Line of
 the SEC. 20 TWP. 20S RGE. 17W

DRILLING CONTRACTOR Salazar
 ADDRESS Box 2958 Milan Station
Grants, New Mexico 87021



WELL PLAT
 (Quarter) or (Full) Section - Please indicate.

PLUGGING CONTRACTOR _____
 ADDRESS _____
 TOTAL DEPTH 2232' PBDT 2132
 SPUD DATE 3-21-81 DATE COMPLETED 10-10-81

ELEV: GR2086DF KB

DRILLED WITH (CABLE) (ROTARY) (AIR) TOOLS
 Report of all strings set - surface, intermediate, production, etc. (New) / (Used) casing.

KCC ✓
 KGS ✓
 MISC. ✓

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	9 7/8	7"	17#	1020	50-50-POZ	300	
Production	6 1/4	4 1/2	10.5	2232	Lite 60-40 POZ	200 150	10% Salt

RECEIVED
 STATE CORPORATION COMMISSION
 DEC 4 1981
 12-4-81

LINER RECORD			PERFORATION RECORD		
Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
TUBING RECORD			5- Selective 90 Gram Jets 2127'-2135'		
Size	Setting depth	Pecker set at	2 22 1/2 Gram Jets 2087'-2092'		

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD	
Amount and kind of material used	Depth interval treated
500 Gal. 15% HCL w/3% Acetic + CLA -Stay	2127'-2135'
500 Gal. 15% MSR, 1500 Gals. 15% NE.	2087'-2092'
Fract w/120 Bbls., 330 MCF N2 & 20000# Sand	" "

TEST DATE: 10-9-81		PRODUCTION	
Date of first production	Producing method (flowing, pumping, gas lift, etc.)	A.P.I. Gravity	
RATE OF PRODUCTION PER 24 HOURS	Oil 0 bbls.	Gas TSTM MCF	Water % 150 bbls.
Disposition of gas (vented, used on lease or sold)		Producing interval(s)	

** The person who can be reached by phone regarding any questions concerning this information.
 A witnessed initial test by the Commission is required if the well produces more than 25 BOPD or is located in a Basic Order Pool.

Name of lowest fresh water producing stratum Cheyenne Depth 230
 Estimated height of cement behind pipe Cement Cir.

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Krider - gas & water	2072	2106	Stone Corral	1130
Winfield Water	2128	2150	Krider	2072
Towanda Water	2189	2218	Winfield	2128
			Towanda	2189
No cores or Tests				
			Ran Guard, Density and Cased hole logs.	Neutron
<p>Note: This well will be given to landowner for irrigation gas.</p>				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

A F F I D A V I T

STATE OF Colorado, COUNTY OF Arapahoe SS,

David S. Dudzik OF LAWFUL AGE, BEING FIRST DULY SWORN UPON HIS

OATH, DEPOSES AND SAYS:

THAT HE IS Chief Engineer FOR Anador Resources, Inc.

OPERATOR OF THE Haas LEASE, AND IS DULY AUTHORIZED TO MAKE THIS

AFFIDAVIT FOR AND ON BEHALF OF SAID OPERATOR, THAT WELL NO. 1-20 ON SAID LEASE HAS

BEEN COMPLETED AS OF THE 10th DAY OF October 19 81, AND THAT ALL

INFORMATION ENTERED HEREIN WITH RESPECT TO SAID WELL IS TRUE AND CORRECT.

FURTHER AFFIANT SAITH NOT.

(S) David S. Dudzik

SUBSCRIBED AND SWORN TO BEFORE ME THIS 2nd DAY OF December 19 81

Kris Ann Rosengren
 NOTARY PUBLIC

MY COMMISSION EXPIRES: My Commission Expires Sept. 15, 1984