

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 -145 -00728:0001 (of this well)

RECEIVED

JUL 26 1976

7-26-1976

Operator's Full Name National Cooperative Refinery Association CONSERVATION DIVISION OF
WICHITA, KANSAS

Complete Address Box 6, Great Bend, Kansas 67530

Lease Name Matoush Well No. 1

Location NE NE SE Sec. 9 Twp. 20 Rge. (E) (W) 19

County Pawnee Total Depth 4222'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Kelso Casing Pulling

Address Box 176, Chase, Kansas 67524 License No. 683

Operation Completed: Hour 10:30 A Day 23 Month 7 Year 1976

The above well was plugged as follows:

Total Depth 4222' 8 5/8 csg set 133' cwc

5 1/2 csg set 4222' cw 100 sk cmt.

5 1/2 csg PBSD 4191' & PFS (4173'-4188').

Filled 5 1/2 csg W/sd (4191'-4150') Dumped 4 sk cmt W/dump bailer. (4150'-4120')

Cutoff & recovered 2800' of 5 1/2 csg.

Sun Cementing Co. squeezed 8 5/8 csg with 25 sk gel & water W/300 lbs hulls, -

released plug & 130 sk 50-50 poz 6% & shutin. PP 500 lbs. SIP 150 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 7/29/76

INV. NO. 3522-U