

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

AUG 3 1964

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name National Co-op Ref Assn.
Complete Address: 305 Rule Bldg Wichita, Kansas
Lease Name Ellis Well No. 2
Location NE SE NE Sec. 9 Twp. 20 Rge. (E) (W) 19
County Pawnee Total Depth 4256
Abandoned Oil Well Gas Well Input Well SWD Well D & A
Other well as hereafter indicated: _____
Plugging Contractor: FX Forbes Casing Pulling
Address: Great Bend, Kans License No. 49
Operation Completed: Hour 9:30AM Day 28 Month 7 Year 64

The Above well was plugged as follows:

8 5/8" 137' circulated with cement - 5 1/2" 4256' with 100 sax cement.
PB to 4222' Perfr 4207'

Sand back to 4200', set 4 sax cement with dump bailer - pulled 3200'
5 1/2" to 600' - circulated hole with heavy mud through 5 1/2" (20 sax Gel),
displaced 20 sax cement through 5 1/2" at 600', heavy mud to 200',
displaced 20 sax cement through 5 1/2" at 200', heavy mud to 35',
cement 35' to 0'.

Mudding and cementing by Forbes Company Pump truck.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 8/3/64
INV. NO. 9571-W

Signed: Edwin P. Kelly
Well Plugging Supervisor