

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

3-30-1965

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

MAR 30 1965

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name National Cooperative Refg Assn
Complete Address: R417 Wichita Plaza Wichita, Kans
Lease Name Ellis Well No. 1
Location SE SE NE Sec. 9 Twp. 20 Rge. (E) (W) 19
County Pawnee Total Depth 4224
Abandoned Oil Well x Gas Well Input Well SWD Well D & A
Other well as hereafter indicated:
Plugging Contractor: J. O. Forbes Casing Pulling & Sun Cementing Co
Address: Great Bend, Kans License No. 49
Operation Completed: Hour 4PM Day 27 Month 3 Year 65

The Above well was plugged as follows:

8 5/8" 245' circulated with cement - 5 1/2" 4220' with 100 sax cement
Perf 4179'

Filled with sand to 4150', set 4 sax cement with dump bailer, pulled
2520' 5 1/2" to 600', circulated hole with heavy gel mud through 5 1/2" at 600',
displaced 20 sax cement through 5 1/2" at 540', heavy mud to 240', displaced
20 sax cement through 5 1/2" at 240', heavy mud to 35', set bridge and 10 sax
cement to bottom cellaf.

Mudding and cementing by Sun Cementing Co.

I hereby certify that the above well was plugged as herein stated.

DATE 3/30/65

Signed: Edson Petty
Well Plugging Supervisor

INV. NO. 898-W

INVOICED