

KANSAS

Form CP-3  
Rev. 6-4-68

## STATE CORPORATION COMMISSION

## CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

RECEIVED  
STATE CORPORATION COMMISSION  
APR 17 1974  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name National Cooperative Refinery Association  
Complete Address Box 6 Great Bend, Kansas 67530  
Lease Name Matoush Well No. 2  
Location SW NE SE Sec. 9 Twp. 20 Rge. (E) (W) 19  
County Pawnee Total Depth 4230'  
Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A         
Other well as hereafter indicated         
Plugging Contractor Southwest Casing Pulling  
Address Box 364, Great Bend, Kansas License No. 399  
Operation Completed: Hour 3:15 P Day 16 Month 4 Year 1974  
The above well was plugged as follows:  
Total Depth 4230' 8 5/8 csg set at 132' cwc  
5 1/2 csg set at 4230' cw 125 sk cem.  
5 1/2 csg PBTD 4210' with perf. (4192-4199)  
Filled 5 1/2 csg W/sd (4210-4150) dumped 5 sk cem W/dump bailer. (4150-4115)  
Cutoff and recovered 3215' of 5 1/2 csg.  
Pumped down 8 5/8 csg with 22 sk gel & water W/300 lbs hulls, -70 sk cement -  
8 sk gel & water -released 8 5/8 plug and pumped 50 sk cement. Max PP 800 lbs.  
SIP 300 lbs. by Allied Cementing Co.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 4/17/74  
INV. NO. 8936-U

Signed: Leo F. Messey  
Well Plugging Supervisor