

R

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 23 1968  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Vincent F. Hiebsch

Complete Address: 625 Union Center Wichita, Kansas

Lease Name Pfenninger Well No. 1

Location 440' SNL 880' WEL of SW/4 Sec. 8 Twp. 20 Rge. 19 (E) (WXX)

County Pawnee Total Depth 4179'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A XX

Other well as hereafter indicated:     

Plugging Contractor: Murfin Drlg.

Address: Wichita, Kansas License No.     

Operation Completed: Hour 8:30P Day 21 Month 12 Year 1968

The Above well was plugged as follows:

RTD 4179' 8 5/8 csg set at 355' cwc. Cmt. Mat. 50-50 poz cmt. W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 660' and displaced 70 sc cmt.

thru drill pipe. Heavy mud to 330' set cementing plug and displaced 20 sc cement thru

drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base

of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo F. Mearns  
Well Plugging Supervisor

INVOICED

DATE 12-23-68

INV. NO. 9087-W