

15.145.01354.0001

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 28 1972  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name National Cooperative Refinery Association  
Complete Address Box 6 Great Bend, Kansas 67530  
Lease Name Hagerman Well No. 8  
Location C S/2 NE SW Sec. 10 Twp. 20 Rge. (E) (W) 19  
County Pawnee Total Depth 4219'  
Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A         
Other well as hereafter indicated         
Plugging Contractor Ralph Comstock Pipe Pulling  
Address Stafford, Kansas 67578 License No. 490  
Operation Completed: Hour 9:45 A Day 25 Month 2 Year 1972

The above well was plugged as follows:

Total Depth 4219' 8 5/8 csg set at 148' cwc 200 sk.  
5 1/2 csg set at 4219' cw 100 sk cmt.  
5 1/2 csg PBSD 4216' with top perf. (4193)  
Filled 5 1/2 csg W/sd (4180-4216) dumped 5 sk cmt W/dump bailer. (4145-4180)  
Cutoff and recovered 2610' of 5 1/2 csg.  
Pumped down 8 5/8 csg with 20 sk gel W/300 lbs hulls, released plug and pumped  
130 sk reg. poz 6% total gel. 200 lbs shutin pres.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: R. J. Mearns  
Well Plugging Supervisor

DATE 2/28/72  
INV. NO. 5229-W