

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

7-26-1976

RECEIVED
STATE CORPORATION COMMISSION

JUL 26 1976

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - - CONSERVATION (of this well)
Wichita, Kansas

Operator's Full Name National Cooperative Refinery Association

Complete Address Box 6, Great Bend, Kansas 67530

Lease Name Hagerman Well No. 4

Location NW NE SW Sec. 10 Twp. 20 Rge. (E) (W) 19

County Pawnee Total Depth 4217'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Southwest Casing Pulling

Address Box 364, Great Bend, Kansas License No. 399

Operation Completed: Hour 1:30 P Day 23 Month 7 Year 1976

The above well was plugged as follows:

Total Depth 4217' 8 5/8 csg set 134' cwc

5 1/2 csg set 4217' cw 125 sx cem.

5 1/2 csg PBD 4195 & PFS (4146-4195) Sand back to 4150' -4 sx cem W/dump bailer.

Cutoff & recovered 3200' of 5 1/2 csg.

Sun Cementing Co. squeezed 8 5/8 csg with 25 sk gel & water W/300 lbs hulls-

released 8 5/8 plug & 130 sk 50-50 poz 6% & shutin. PP 400 lbs. SIP 100 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Mussey
Well Plugging Supervisor

DATE 7/29/76

INV. NO. 3520-U