

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
7-26-1976
JUL 26 1976

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - - (of this well)

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name National Cooperative Refinery Association

Complete Address Box 6, Great Bend, Kansas 67530

Lease Name Hagerman Well No. 5

Location SW NW NW Sec. 10 Twp. 20 Rge. (E) (W) 19

County Pawnee Total Depth 4266'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Southwest Casing Pulling

Address Box 364, Great Bend, Kansas License No. 399

Operation Completed: Hour 11:30 A Day 23 Month 7 Year 1976

The above well was plugged as follows:

Total Depth 4266' 8 5/8 csg set 169' cwc

5 1/2 csg set 4266' cw 135 sx cem.

5 1/2 csg PBD 4248' & PFS (4287'-4211')

Filled 5 1/2 csg W/sd (4248'-4150') dumped 4 sk cem W/dump bailer. (4150'-4120')

Cutoff & recovered 3120' of 5 1/2 csg.

Sun Cementing Co. squeezed 8 5/8 csg with 25 sk gel & water W/300 lbs hulls -

released plug & 130 sk 50-50 poz 6% A&shutin. PP 750 lbs. SIP 150 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Messing
Well Plugging Supervisor

DATE 7/29/76

INV. NO. 3523-U