

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 -145-01434.0000 (of this well)

REC-
STATE CORPORATION
JUL 25 1978
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name National Cooperative Refinery Assoc.

Complete Address Box 6, Great Bend, Kansas 67530

Lease Name Hagerman Well No. 3

Location SW SE NW Sec. 10 Twp. 20 Rge. (E) (W) 19

County Pawnee Total Depth 4195'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Kelso Casing Pulling

Address Box 176, Chase, Kansas 67524 License No. 683

Operation Completed: Hour 12:25 P Day 24 Month 7 Year 1978

The above well was plugged as follows:

Total Depth 4195' 8 5/8 csg set 131' cwc

5 1/2 csg set 4194' cw 75 sk cem.

4 1/2 csg PBTB 4193' & perf. (4160'-4186')

Filled 5 1/2 csg W/sd (4193'-4145') dumped 4 sk cem. W/dump bailer. (4145'-4115')

Cutoff & recovered 780' of 5 1/2 csg.

Sun Cementing Co. mixed & pumped down 8 5/8 csg with 10 sk gel & water W/200 lbs hulls,
released plug & pumped 125 sk 50-50 poz 6% & shutin. FPP 800 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 7-25-78
INV. NO. 7736-W

Signed: [Signature]
Well Plugging Supervisor