

R

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - -

RECEIVED
STATE CORPORATION COMMISSION
JUL 25 1978
CONSERVATION DIVISION
Wichita, Kansas

(of this well)

Operator's Full Name National Cooperative Refinery Assoc.

Complete Address Box 6, Great Bend, Kansas 67530

Lease Name Hagerman Well No. 2

Location NW NW SW Sec. 10 Twp. 20 Rge. (E) (W) 19

County Pawnee Total Depth 4220'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Kelso Casing Pulling

Address Box 176, Chase, Kansas 67524 License No. 683

Operation Completed: Hour 11:15 A Day 24 Month 7 Year 1978

The above well was plugged as follows:

Total 4220' 8 5/8 csg set 133' cwc

5 1/2 csg set 4219' cw 75 sk cem.

5 1/2 csg PBSD 4214' & perf. (4151'-4203')

Filled 5 1/2 csg W/sd (4214'-4135') dumped 4 sk cem W/dump bailer. (4135'-4105')

Cutoff & recovered A/2420' of 5 1/2 csg.

Sun Cementing Co. mixed & pumped down 8 5/8 csg with 20 sk gel & water W/200 lbs

hulls, released plug & pumped 125 sk 50-50 poz 6% & shutin. FPP 800 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Massey
Well Plugging Supervisor

DATE 7-25-78

INV. NO. 7735-W