

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

JAN 2 1963

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name National Coop Refining Assn.

Complete Address: Box 6, Great Bend, Kansas.

Lease Name Hagerman #6 Well No. #6

Location NW-SW-SW Sec. 10 Twp. 20 Rge. 19 (E) (W) X

County Pawnee County Total Depth 4252'

Abandoned Oil Well x Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Forbes Caseing Pulling Co.

Address: Box 221 Great Bend, Kansas. License No.

Operation Completed: Hour 4:PM Day 21 Month Dec. Year 1962

The Above well was plugged as follows:

4253' of 5 1/2" long string cemented with 125 sacks cement. Hole plugged
back to 4234' Top perforation at 4178' , sanded to 4170' , 5 sacks cement.
135' of 8 5/8" surface pipe circulated with cement. Hole filled with mud
to 120' , 10' rock bridge and 20 sacks cement. Hole filled to 40' with mud, 10'
rock bridge and 10 sacks cement to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 1/4/63

INV. NO. 6359-W

Signed: William Justus
Well Plugging Supervisor