

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

JAN 2 1963

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name National Cooperative Refining Assn.

Complete Address: 305 Rule Bldg. Wichita, Kansas.

Lease Name Hagerman # 7 Well No. #7

Location SE-NW-SW Sec. 10 Twp. 20 Rge. 10 (E) (W) X

County Pawnee County Total Depth 4234'

Abandoned Oil Well x Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Forbes Caseing Pulling Co.

Address: Box 221 Great Bend, Kansas. License No.

Operation Completed: Hour 6:PM Day 18 Month Dec. Year 1962

The Above well was plugged as follows:

~~4234' of 5 1/2" long string. Plugged to 4186'. Top perforation at 4161',
sanded to 4150' & 5 sacks cement. 130' of 8 5/8" surface pipe circulated
with cement. Hole filled to 120' with mud, 10' rock bridge & 20 sacks
cement. Hole filled to 40' with mud, 10' rock bridge and 10 sacks
cement to base of cellar.~~

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 1/4/63

INV. NO. 6354-W

Signed: Herman Justice
Well Plugging Supervisor