

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUL 8 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Beardmore Drilling Company
Complete Address: 700 -- 120 bldg., Wichita, Kansas
Lease Name Miller "B" Well No. 1
Location Approx NW NW Sec. 8 Twp. 20 Rge. 20 (E) (W) X
County Pawnee Total Depth 4368
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated:
Plugging Contractor: Rains & Williamson
Address: Wichita, Kansas License No.
Operation Completed: Hour 11 A Day 2 Month 6 7 Year 1968

The Above well was plugged as follows:

RTD 4368' 8 5/8 csg set at 312' cwc 200 sc. Cem. Mat. 100sc 50-50 poz cem. W/6% total gel
Gunned pits, circulated heavy mud, set cementing plug at 660' and displaced 70 sc cem.
thru drill pipe. Heavy mud to 300' set cementing plug and displaced 20 sc cement thru
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base
of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo J. Messing
Well Plugging Supervisor

INVOICED

DATE 7/9/68
INV. NO. 8069-U